

## ADDENDUM NUMBER 1

DATE OF ADDENDUM: September 2, 2016

DIVISION OF MINERAL RESOURCES MANAGEMENT  
OHIO DEPARTMENT OF NATURAL RESOURCES  
2045 MORSE ROAD  
BUILDING H-2  
COLUMBUS, OHIO 43229-6693

### BID OPENING DATE REMAINS SEPTEMBER 15, 2016 AT 1:30 PM.

To the Conditions and Specifications for:

EAST CADIZ WATER LINE MAINTENANCE  
HARRISON COUNTY, OHIO  
ODNR PROJECT NUMBER HR-Gr-29

All Bidders are reminded to acknowledge receipt of the Addendum in the space provided on the Form of Proposal, when submitting a bid.

#### TO ALL BIDDERS:

This Addendum, modifying the original contract conditions and specifications, shall be taken into account in preparing Proposals and is hereby made part of the Contract documents.

#### NOTICE TO BIDDERS:

To account for added line item, the Engineer's Estimate has been revised to **\$72,155**.

#### BID SCHEDULE:

The attached Bid Schedule must be used to submit an acceptable bid. The changes made are:

- a. Added Line Item 2120 Clearing and Grubbing

#### DETAILED SPECIFICATIONS

*The following specification and line item will be added to the Contract.*

#### 2120 CLEARING AND GRUBBING

- A. Description. This item shall consist of furnishing all labor and equipment necessary to clear the trees along County Road 5's ditch bank where underdrain is installed. This item shall also include the removal of all cleared material not retained by the landowner from the project site. **Note this includes the two (2) trees/tree groups noted on the construction drawings as "Tree Not To Be Disturbed"**.

The Chief shall exercise control over clearing and shall designate all trees, plants, shrubs, etc., to be removed or to remain. This work shall also include the preservation from injury or defacement of all trees designated to remain. Burning of debris materials is not permitted.

Trees shall be cut off flush with the ground and stumps left in place. **The stumps/root ball for all trees shall not be removed and remain in place other than grubbing of roots within the underdrain trench.** Trees shall be cut into standard 8-foot length logs. All firewood logs, defined as those greater than 6-inches shall be cut, topped, and neatly

stacked **along access/staging area at location mutually agreed upon by the landowner and the Chief.** All trees, tree tops and limbs less than 6-inches shall be removed and disposed of at an approved off site disposal location. All costs for the removal, disposal and hauling of this material shall be considered incidental to this item.

Clearing and grubbing for a particular area shall be completed prior to beginning underdrain installation and earthwork operations. If Contractor clears and grubs beyond the indicated areas, whether knowingly or accidentally, the Contractor shall replant and otherwise restore all areas outside the limits to the existing condition, prior to start of work, at his/her own expense.

- B. Payment. The cost of this work shall be included in the contract lump sum price for "Clearing and Grubbing".

APPROVED:

Thomas Wiley, P.E.  
Thomas Wiley, P.E.  
Division of Mineral Resources Management

DATE: 09/02/16

