

**STATE OF OHIO
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF MINERAL RESOURCES MANAGEMENT**

**STOOKESBERRY DEMOLITION
COLUMBIANA COUNTY, OHIO
PROJECT NUMBER: CL-EI-35**

PROJECT DESCRIPTION

A. Description:

The intent of this project is to demolish an abandoned coal mine wash plant foundation. The structure consists of reinforced concrete and structural steel. The ruins have created a hazard that poses a threat to public health and safety. The project includes dewatering the foundation and the removal of the concrete and steel. The area in and around the wash plant shall be resoiled and revegetated to prevent erosion and sedimentation.

B. Construction Entrance

Access to the site shall consist of improving and existing aggregate utility drive and constructing a staging area adjacent to the abandoned foundation.

C. Demolition

Reinforced concrete and structural steel shall be demolished on site and trucked to a licensed landfill facility.

D. Restoration

Six (6) inches of topsoil shall be placed in the areas indicated on the plans, the foundation pit filled, and vegetation established to prevent erosion and sedimentation.

E. Major work items include:

Mobilization.

Surveying and construction layout stakes.

Construction of an access road and staging area utilizing No. 3 and No. 4 crushed limestone.

Maintaining traffic along U.S. 30 / S.R. 45 and Stookesberry Road.

Clearing and grubbing approximately 0.25 acres. Offsite removals of stumps are incidental to Clearing and Grubbing.

The treatment (as required) and dewatering of approximately 9,000 gallons of water.

The Installation of approximately 862 linear feet of ODOT Type "C" silt fence and a temporary sediment basin.

Demolition of reinforced concrete and structural steel foundation.

Debris removal including reinforced concrete, steel, and other onsite debris.

Resoiling of site.

Re-vegetation of approximately two (2) acres including lime, seed, mowing, and fertilizer.

The reclamation of the staging area.

Removal of sediment control devices.

F. The following ODNR-DMRM staff, from the Salem Office, is involved with this project and may be contacted with any questions or concerns.

<u>Project Officer:</u>	Jeffery Clarke	330-222-1527
<u>Project Engineer:</u>	Justin Conkle, P.E.	330-222-1527

**STOOKESBERRY DEMOLITION
COLUMBIANA COUNTY, OHIO
PROJECT NUMBER: CL-EI-35**

DIRECTIONS TO PROJECT SITE

The Stookesberry Demolition project is located near the intersection of Stookesberry Road (CR 417) and State Route 45 / U.S. Route 30. A home is located near the site at 11290 U.S. 30, Lisbon Ohio, The mandatory pre bid meeting will be held at the site.

A. From Ashtabula and North:

Merge onto OH-11 S - 50.4 mi

Take the exit onto I-80 W/OH-11 toward Girard/Cleveland, Keep left at the fork to continue on OH-11, follow signs for Canfield - 25.8 mi

Take the OH-154 exit toward US-30 W/Rogers/Lisbon - 0.3 mi

Turn right onto OH-154 W - 1.7 mi

Turn left onto U.S. 30 E/Jackson St Continue to follow U.S. 30 E - 3.0 mi

Site entrance is at the intersection of Stookesberry Road and US 30 on the left side.

B. From East Liverpool and South:

Turn left onto the Route 30/Ohio 39 W ramp to Route - 11 0.2 mi

Merge onto U.S. 30 W - 9.3 mi

Take the US-30 W exit toward OH-45/W Point/Lisbon/Rodeo - 0.3 mi

Turn left onto U.S. 30 W - 3.2 mi

Site entrance is at the intersection of Stookesberry Road and US 30 on the right side.

C. From Pennsylvania and East:

Take the exit onto I-80 W toward Youngstown Entering Ohio - 16.9 mi

Keep left at the fork to continue on OH-11, follow signs for Canfield - 25.8 mi

Take the OH-154 exit toward US-30 W/Rogers/Lisbon - 0.3 mi

Turn right onto OH-154 W - 1.7 mi

Turn left onto U.S. 30 E/Jackson St Continue to follow U.S. 30 E - 3.0 mi

Site entrance is at the intersection of Stookesberry Road and US 30 on the left side.

D. From the Pittsburgh Area

Merge onto I-376 W - 0.6 mi

Keep left to stay on I-376 W - 5.4 mi

Keep left to stay on I-376 W - 11.8 mi

Take exit 52 toward US-30/Clinton - 0.2 mi

Turn left onto Clinton Rd (signs for US-30) 1.1 mi

Turn right onto U.S. 30 W Entering West Virginia - 19.6 mi

Use any lane to take the US 30 W/Ohio 39 W exit toward E Liverpool/Ohio - 11 N

Entering Ohio - 0.4 mi

Continue onto U.S. 30 W - 10.4 mi

Take the US-30 W exit toward OH-45/W Point/Lisbon/Rodeo - 0.3 mi

Turn left onto U.S. 30 W - 3.2 mi

Site entrance is at the intersection of Stookesberry Road and US 30 on the right side.

E. From Cleveland and Northwest:

Merge onto I-77 S 5.4 mi

Keep left to stay on I-77 S 9.4 mi

Take exit 146 toward I-80/Toledo/Youngstown 0.8 mi

Keep left, follow signs for Interstate 80/Ohio Turnpike - 0.4 mi

Keep right at the fork, follow signs for I-80 E/Youngstown and merge onto I-80 E/Ohio Turnpike - 45.0 mi

Use the right 2 lanes to take exit 218 for I-80 E - 0.9 mi

Use the left lane to keep left at the fork and follow signs for Mahoning Ave/OH-18 – 0.2 mi

Keep left and merge onto I-80 E - 4.1 mi

Take exit 224A for OH-11 S toward Canfield - 0.5 mi

Merge onto OH-11 - 25.0 mi

Take the OH-154 exit toward US-30 W/Rogers/Lisbon - 0.3 mi

Turn right onto OH-154 W - 1.7 mi

Turn left onto U.S. 30 E/Jackson St Continue to follow U.S. 30 E - 3.0 mi

Site entrance is at the intersection of Stookesberry Road and US 30 on the left side.

REFER TO THE FOLLOWING PAGE FOR THE LOCATION MAP

The pre-construction meeting will be held at the site.

